

सूचना आमंत्रण कोटेशन(एनआईक्यू)/NOTICE INVITING QUOTATION (NIQ)

विषय: निफ्ट परिसर, धर्मशाला में आंतरिक एवं बाह्य छात्रावास, शैक्षणिक ब्लॉक और आंतरिक छात्रावास के भोजनालय के फर्श/दीवार के टाइल्सों के रखरखाव/मरम्मत करने हेतु कोटेशन के संबंध में।

Sub : Repair/maintenance of floor/wall tiles of inside & outside ladies hostel, academic block and inside hostel mess at NIFT campus, Dharmasala.

एनआईएफटी-कन्नूर एनआईएफटी परिसर, धर्मशाला, कन्नूर में महिला छात्रावास (अंदर और बाहर), शैक्षणिक ब्लॉक और आंतरिक छात्रावास के भोजनालय के फर्श/दीवार के टाइल्सों के रखरखाव / मरम्मत के लिए प्रतिष्ठित ठेकेदारों से उद्धरण आमंत्रित करता है, जैसा कि अनुलग्नक -1 में संलग्न विवरण है। हम आपसे अनुरोध करते हैं कि आप संलग्न प्रारूप में अपनी सर्वश्रेष्ठ/प्रतिस्पर्धी दरें हाथ/डाक/कूरियर के माध्यम से जमा करें ताकि निदेशक, राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, निफ्ट परिसर, मंगट्टुपरम्बा, कन्नूर-670562 तक 27.06.2025 को शाम 4.30 बजे या उससे पहले पहुंच सकें।

NIFT - Kannur invites quotation from reputed contractors for repair/maintenance of floor/wall tiles of ladies hostel (inside & outside), academic block and inside hostel mess at NIFT campus, Dharmasala, Kannur as per details enclosed in Annexure-I. We request you to submit your best / competitive rates in the enclosed format hand/post/courier so as to reach to the Director, National Institute of Fashion Technology, NIFT campus, Mangattuparamba, Kannur-670562 on or before 27.06.2025 at 4.30PM

निबंधन व शर्तें/Terms and conditions:

1. सभी समावेशी (कर, शुल्क, परिवहन, लोडिंग अनलोडिंग शुल्क आदि) दरें उद्धृत की जाएंगी।
All-inclusive (Taxes, duties, transportation, loading unloading charges etc) rates to be quoted.
2. आपको अनुलग्नक-1 के अनुसार कोट प्रस्तुत करना है।
You have to submit the quote as per Annexure-I
3. संविदाकार को यह सलाह दी जाती है कि उन्हें अपने दरों को कोट करने के पूर्व साइट पर आकर कार्य की जरूरत और स्पष्टीकरण की जांच करें यदि कोई हो तो।
Contractors are advised to visit the onsite to check the requirement of the work and clarification if any before quoting their rates.
4. आगे की स्पष्टीकरण हेतु कृपया आदर्श ए (9061801675) से संपर्क करें।
For further clarification, may please call Adarsh A (9061801675)
5. यह कार्य कार्य आदेश के जारी होने के 10 दिनों के अंदर संपन्न किया जाएगा।

The work will be completed within 12 days of issue of work Order.

6. पैन कार्ड और जीएसटी पंजीकरण सं की प्रूफ संलग्न करें।

Attach the proof of PAN card and GST registration No.

7. भुगतान 10 कार्य दिवस के भीतर भवन विभाग और वास्तविक माप के आधार पर संतोषजनक पूर्णता के खिलाफ किया जाएगा।

The payment will be made against satisfactory completion by building department and actual measurement basis within 10 working days.

(प्रो. डॉ. मनोज तिवारी/Prof Dr. Manoj Tiwari)

(संयुक्त निदेशक (प्रभारी)/Joint Director (I/C))

सूची के अनुसार सूचना-पट्ट पर प्रदर्शन हेतु प्रतिलिपि:

Copy for display on the notice board as per the list:

1. Muncipal Office Anthoor
2. Village Office, Morazha
3. NIFT campus Kannur Notice Board

(Annexure-I)

Name of work: Repair/maintenance of floor/wall tiles of inside & outside ladies hostel, academic block and inside hostel mess at NIFT campus, Dharmasala.					
SI No	Item Description	Unit	Quantity	Rate	Amount
1	Dismantling tile work in floors and walls laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm.	Sqm	69		
2	Providing and laying of Vitrified tiles in floor of size 600mm x 600mm (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).	Sqm	56		
3	Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in-charge.	Sqm	56		
4	Providing and fixing 1st quality ceramic glazed wall tiles of size(30x20) conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	8		
5	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.				
5.1	Glazed Vitrified tiles Matt/Antiskid finish of size 600 x 600 mm	Sqm	4.3		
Total Amount(Rs)					
GST Amount(Rs)					
Grand Total(Rs)					
Total Amount in words:					
.....					
.....					

Supplier Name:

Signature with office seal:

Contact Number: