



राष्ट्रीय फैशन टेक्नालॉजी संस्थान
(वस्त्र मंत्रालय, भारत सरकार)

National Institute of Fashion Technology
Ministry of Textiles, Govt. of India
(An ISO 9001:2008 certified institute)

11.05.2018

QUOTATION NOTICE

NIFT – Kannur invites quotation from the qualified contractors for the following civil works. Intending contractors who have GST registration may submit the quotation in the following works and submit the same by post/courier/ by hand so has to reach National Institute of Fashion Technology, NIFT campus, Mangattuparamba, Kannur – 670562 on or before 16.05.2018,5.30PM.

Sl. No.	Name of Work	Last date for receipt of duly filled in quotations
1.	Providing Nylon net on GI pipe post side protection masonry work, leveling to volley ball court, covering slab to drain in NIFT, Campus, Kannur .	16.05.2018, 5.30 PM

Note: Quotation schedule will be given by the NIFT to the contractors free of cost on request up to **16.05.2018, 1.00 PM**

Terms & Conditions

1. Rates inclusive of all taxes, duties, transportation, loading, unloading charges etc.,
2. The work will be completed within 30 days of issue of work order.
3. Attach the proof of PAN Card and GST Registration No.
4. Payments will be made within 15 days against satisfactory completion of the work and acceptance of the items by competent authority.


11/5/18
ASSISTANT DIRECTOR

Copy for display in the notice board as per list:

1. Municipal office, Anthoor.
2. Govt. Engineering Collage, Kannur.
3. Village office , Morazha.
4. NIFT, Kannur


11/5/18

A Premier Institute of Design, Management & Technology
Set up under an Act of Parliament

NIFT Campus, Dharmasala, Kanoor (P.O.), Kalliasseri, Kannur, Kerala - 670 562
t + 0497 2784780 to + 0497 2784786 | f + 0497 2784785 | e info.kannur@nift.ac.in

www.nift.ac.in/kannur

PROVIDING NYLON NET ON G I PIPE POST,SIDE PROTECTION MASONRY WORK,LEVELING TO VOLLEY BALL COURT ,COVERING SLAB TO DRAIN IN NIFT CAMPUS KANNUR

SI No	Quantity	Description	Per Unit	Quoted rates (Rs.) in figure and words	Amount (Rs.)
1	22Nos	Excavating holes more than 0.10cum & up to 0.50cum including getting out the excavated earth disposing of surplus excavated earth as directed with in a lead of 50m and lift up 1.50m (D S O R 2-30-1)	Each		
2	2M ³	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:5;10 using 40mm stone aggregate (D S O R 4-1-10)	1M ³		
3	1M ³	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth 1:2:4 using 20mm stone aggregate (D S O R 4-1-3)	1M ³		
4	4.60M ³	Reinforced cement concrete 1:1½:3 using 20mm broken stone excluding cost of centering cost of reinforcement including all cost of cement sand broken stone and its labour charge (D S O R 2-2-1)	1M ³		
5	29M ²	Centering and shuttering including strutting of and removal of form work for suspended floor roof landing balconies and access platform (D S O R 5-9-3)	1M ²		
6	290Kg	Steel reinforcement for R C C work including straightening cutting bending placing in position and binding all complete up to plinth level thermo-mechanical treated bar (D S O R 5-22-6)	1kg		
7	530M ²	Providing and fixing nylon net for covering around of the valley ball court after fixing the pipe post vertical and horizontal as per direction of Engineers -in-charge fixing the pipe together with swivel coupler, brackets, G I pipe and net with nylon thread or metal wire, including all labour charge for hoisting pipe stay in position for concreting including cost of nylon net, thread but excluding cost of G I pipe, swivel coupler, brackets etc complete (Local market rate)	1M ²		
8	33M ³	Earth work in rough excavation banking excavated earth in layer not exceeding 20cms depth breaking clods watering rolling each layers with wooden or steel rammers filling up ground depression lead up to 50 and lift upto 1.50m all kind of soil (D S O R 2-2-1 modified)	1M ³		
9	9.60M ³	Laterite masonry with neatly dressed laterite stone of size 40x20x15cms or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials labour charges etc complete	1M ³		
10	100M ²	Plastering with Cement mortar 1:6 thick one coat floated hard and trowelled smooth including watering curing cost of materials labour charges etc complete for plastering (D S O R 13.1.2)	1M ²		
Total Amount (Rs.)					
In Words					

Contractor