



राष्ट्रीय फैशन टेक्नालॉजी संस्थान
(वस्त्र मंत्रालय, भारत सरकार)

National Institute of Fashion Technology
Ministry of Textiles, Govt. of India
(An ISO 9001:2008 certified institute)

17.05.2019

कोटेशन नोटिस
QUOTATION NOTICE

निफ्ट - कन्नूर निम्नलिखित सिविल कार्यों के लिए योग्य ठेकेदारों से उद्धरण आमंत्रित करता है।
NIFT – Kannur invites quotation from qualified contractors for the following civil works.

क्रमांक Sl.No	कार्य विवरण Name of Work	कोटेशन में विधिवत भरा हुआ प्राप्त करने की अंतिम तिथि Last date for receipt of duly filled in quotations
1.	निफ्ट कन्नूर में नाबदान पानी की टंकी के पास बस शेड उपलब्ध कराना Providing bus shed near sump water tank in NIFT Kannur	28.05.2019, शाम 5.00 बजे 28.05.2019, 5.00 PM

जिन ठेकेदारों के पास जीएसटी पंजीकरण है, वे निर्धारित प्रारूप / अनुसूची में कोटेशन जमा कर सकते हैं और पोस्ट / कूरियर / द्वारा हाथ से प्रस्तुत कर सकते हैं ताकि राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, निफ्ट परिसर, मंगट्टुपारम्बा, कन्नूर - 670562 या 28.05.2019, 5.00 बजे से पहले पहुंच सकें।

28.05.2019, दोपहर 1.00 बजे तक अनुरोध पर निफ्ट कार्यालय से उद्धरण अनुसूची एकत्र की जा सकती है

Intending contractors who have GST registration may submit the quotation in the prescribed format/schedule and submit the same by post/courier/ by hand so as to reach National Institute of Fashion Technology, NIFT campus, Mangattuparamba, Kannur – 670562 on or before 28.05.2019, 5.00 PM.

Quotation schedule can be collected from NIFT office free of cost on request up to **28.05.2019, 1.00 PM**

नियम एवं शर्तें / **Terms & Conditions**

- सभी करों, परिवहन, लोडिंग, अनलोडिंग शुल्क आदि को शामिल करते हुए दरें / Rates shall be inclusive of all taxes, transportation, loading, unloading charges etc.,
- चयनित ठेकेदार 7 दिनों के भीतर अनुबंध की राशि के 5% के प्रदर्शन की गारंटी (नकद या डीडी खरीदें) प्रस्तुत करेगा, जिसे कार्य के संतोषजनक रूप से पूरा होने की तारीख से एक वर्ष के लिए रखा जाएगा। / The selected contractor shall furnish performance guarantee (Buy cash or DD) of 5% of the contract amount within 7 days which will be retained for one year from date of satisfactory completion of the work.

A Premier Institute of Design, Management & Technology
Set up under an Act of Parliament

NIFT Campus, Dharmasala, Kanool (P.O.), Kalliasseri, Kannur, Kerala - 670 562
t + 0497 2784780 to + 0497 2784786 | f + 0497 2784785 | e info.kannur@nift.ac.in

www.nift.ac.in/kannur

3. चयनित ठेकेदार 200 / - रुपये के मूल्य के गैर-न्यायिक स्टांप पेपर में एक समझौते को निष्पादित करेगा (रुपए दो सौ रुपये) / The selected contractor shall execute an agreement in non-judicial stamp paper of value of Rs.200/-(Rupees Two Hundred only)
4. वर्क ऑर्डर जारी होने के 30 दिनों के भीतर काम पूरा हो जाएगा। / The work will be completed within 30 days of issue of work order.
5. पैन कार्ड और जीएसटी पंजीकरण संख्या का प्रमाण संलग्न करें / Attach the proof of PAN Card and GST Registration No.
6. सभी वैधानिक कटौती जैसे टीडीएस, वर्कर्स वेलफेयर सेस आदि को नियमानुसार बिलों से वसूला जाएगा। / All statutory deductions such as TDS, Workers Welfare Cess etc. will be recovered from bills as per rules.
7. सक्षम प्राधिकारी द्वारा काम के संतोषजनक समापन और वस्तुओं की स्वीकृति के खिलाफ 15 दिनों के भीतर भुगतान किया जाएगा। / Payments will be made within 15 days against satisfactory completion of the work and acceptance of the items by competent authority.



ओ एस डी परचेस
OSD PURCHASE

सूची के अनुसार नोटिस बोर्ड में प्रदर्शित करने के लिए कॉपी करें:

Copy for display in the notice board as per list:

1. नगर कार्यालय, एंथूर / Municipal office, Anthoor.
2. ग्राम कार्यालय, मोरझा / Village office, Morazha.
3. निफ्ट, कन्नूर वेबसाइट और नोटिस बोर्ड। / NIFT, Kannur website & Notice Board.

PROVIDING BUS SHED NEAR SUMP WATER TANK IN NIFT KANNUR

Quotation Schedule

Sl. No.	Description	Qty.	Unit	Rate (Rs.) Figure and words	Amount (Rs.)
01	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	786	1Kg		
02	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self-tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	132	1m ²		
03	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:	64	1m ²		
04	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -	0.70	1M ³		

	All work up to plinth level: 1:1/2:3 (cement : 11/2 coarse sand : 3 graded stone aggregate 20 mm nominal size)				
05	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm ²), counter sunk head, comprising of 10 m dia polyamide P A 6 grade sleeve, including drilling of hole in frame, concrete/masonry, etc. as per direction of Engineer-in-charge.	10	1No.		
06	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	1.7	1M ³		

Total Amount: (Rs.).....

In words:

Name of the contractor :

Address :

Contractors Registration Number :

Contact Number :

Signature :