



राष्ट्रीय फैशन प्रौद्योगिकी संस्थान  
( वस्त्र मंत्रालय , भारत सरकार )

**National Institute Of Fashion Technology**  
(Ministry of Textiles, Govt. of India)

No. 4750(1)/Rep. & Maint./Office & Bldg/2014/Vol-I (PART-II)

Date: 02.07.2019

### **NOTICE INVITING QUOTATIONS**

Sealed Quotations are invited on behalf of National Institute of Fashion Technology, Navi Mumbai Center from Registered Contractor of CPWD, MPWD, MES, etc., & who have worked with Government Departments, reputed agencies who have carried out similar nature of works on item rate basis as per the requirement and details given in the schedule of items enclosed herewith.

The sealed quotation shall be super scribed with "**Quotation for Repairs to flooring at Girls hostel plot No.15 and Academic block – 2, 3<sup>rd</sup> floor, at NIFT, Kharghar, Navi Mumbai**", and to be submitted in the tender/quotation box kept at the ground floor of 'Administrative' block, NIFT campus, Navi Mumbai before **03.00 P.M. on 09.07.2019**. The quotations will be opened on the same day after 03.30 P.M.

The site can be inspected from 9.00am to 5.30 p.m. during working hours on any working days.

The NIFT reserves the right to accept or reject any quotation in part or whole without assigning any reason thereof.

#### General Terms & Conditions:

1. The rates shall include cost of labours & cost of material, transportation etc., complete in all respects for BOQ.
2. The agency must enclose copy of PAN Card of the company/individual/Firm.
3. The Agency must enclose copy of GST registration.

Seal & Signature of the Agency

Date:

  
Joint Director

डिजाईन, मैनेजमेंट तथा टेक्नालॉजी का महाविद्यालय  
**A Premier Institute of Design, Management & Technology**

A statutory body under the NIFT Act 2006

Page 1 of 6

निफ्ट कॅम्पस, प्लॉट नं. 15, सेक्टर 4, खारघर, नवी मुंबई - 410 210.

NIFT Campus, Plot No.15, Sector - 4, Kharghar, Navi Mumbai - 410210.

t: + 91 022 2774700 +91 022 27747100 | f: + 022 27745386 | e: nift.mumbai@nift.ac.in

www.nift.ac.in



4. The copy of the registration certificate, if any is to be submitted along with the quotation.
5. The Agency must sign with seal on every page of the document.
6. In case of any dispute raised by the Agency, a representation will be made only by the authorized representative of the Agency and the decision of the Director NIFT – Mumbai will be binding on the supplier.
7. The quoted rates shall include all taxes, duties, GST etc. as applicable and no extra shall be payable on this account.
8. After completion of the work rubbish to be removed from the site no additional payment will be made this account.
9. The work has to be completed within a period of 15 days from date of issue of letter of award.
10. The Quote should be submitted in NIFT prescribed format only and conditional quotes shall not be considered.
11. Payment will be made as per the actual quantity and measurement no additional payment will be made.
12. Payment will be made after satisfactory completion of work and submission of original bill.
13. It is mandatory to quote for all the items of the price bid and L-1 will be decided on the basis of total quoted amount. If no item has been quoted it will be deemed to have been included in the quoted rates.
14. No payment shall be made in advance.

Address:  
The Director  
National Institute of Fashion Technology,  
Plot No.15, Sector-4, Kharghar  
Navi Mumbai-410210

Seal & Signature of the Agency

Date:

  
Joint Director



## DETAILS OF THE AGENCY / TENDERER

Name of the Agency/Tenderer : \_\_\_\_\_  
Name of the authorized person : \_\_\_\_\_  
Address of the Agency : \_\_\_\_\_  
  
Phone No.(land line no.) : \_\_\_\_\_  
Mobile No. : \_\_\_\_\_  
Email ID : \_\_\_\_\_  
GST No. : \_\_\_\_\_  
PAN No. : \_\_\_\_\_  
Date of Submission : \_\_\_\_\_

**LAST DATE OF SUBMISSION of QUOTATION: 09.07.2019 by 3.00 p.m.**  
**DATE OF OPENING OF QUOTATION : 09.07.2019 by 3.30 p.m.**

Encl: Price Schedule

Seal & Signature of the Agency

Date:

  
Joint Director

## PRICE SCHEDULE

Name of work: Repairs to flooring at Girls hostel plot No.15 and Academic block – 2, 3<sup>rd</sup> floor, at NIFT, Kharghar, Navi Mumbai.

Sr.No.	Description	Unit	Qty.	Rate in Rs.	Amount in Rs.
1	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	Sqm.	20		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm.	27.3		
3	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Sqm.	7.3		
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to	Sqm.	0.92		

Seal & Signature of the Agency

Date:

  
 Joint Director

	edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade: Area of slab upto 0.50 sqm				
5	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.	RMT	5		
6	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	RMT	5		
7	Cutting of existing cement mortar /concrete strip 150mm depth up to 50 mm dia and providing PVC 50 mm dia pipe up to 60 cm long and closing with repair cement mortar including cos tof all materials and labour charges etc., complete as per direction of the Engineer in charge.	Each	9		
8	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	Sqm.	1.1		
9	Providing and fixing With 20 mm thick beveled tegular mineral fibre false work as per existing thickness up to 20mm, material, specification including cost of all materials charges and laboure charges etc., complete as per direction of Engineer in charge.	Sqm.	1.1		
10	Opening the Existing tile joints by applying heavy duty tile cleaner acid, then brushing the joint and tile surface, then cleaning the tile surface by the jet pump if required then filling the tile joints by water proof material by means of grouting then cleaning the tile surface by the cotton making good	Sqm.	105		

Seal & Signature of the Agency

Date:

  
Joint Director

	including cost of all material labour charges etc., complete as per direction of Engineer in charge.				
11	Supplying of vetrified tiles (thickness to be specified by the manufacturer) Size of tiles 600mmx600mm	Sqm.	11		
12	Laying of existing vitrified floor tiles in different sizes laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete	Sqm.	21		
13	Providing and forming drip mould at beam by using heigh polymerized selp curing mortar as per approved brand etc., complete including cost of labour and material charges etc., complete as per direction of Engineer in charge.	Rmt.	11.5		
	Sub total				
	GST @ _____%				
	Total				
Total amount in words: Rupees _____					
_____					
only					

Seal & Signature of the Agency

Date:

  
Joint Director