



NATIONAL INSTITUTE OF FASHION TECHNOLOGY,
PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210

BRIEF OF QUOTATION

4761/Bldg./Barbed wire fencing/2015

Date: 17/07/2020

Name of work: Repairing of existing windows and other works at AD workshop & Canteen which is damaged due to Cyclone Nisarga at NIFT Campus, Plot No. 15, Sector-4, Kharghar, Navi Mumbai.

Sr. No.	Description of Work	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1.	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	90.00		
2.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass	Sqm	27.25		

Seal and signature of the Agency

Date:


Joint Director



**NATIONAL INSTITUTE OF FASHION TECHNOLOGY,
PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210**

	panes of 5 mm thickness (weight not less than 12.50 kg/ sqm) (AD work shop 17.25+Canteen10.00=27.25)				
3.	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge. (AD work shop 17.25+Canteen10.00=27.25)	Sqm	27.25		
4.	Dismantling roofing and stacking the material within 50 metres lead of: Plastic sheet	Sqm	9.00		
5.	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick corrugated (2.5" or 4.2" or 6") or step-down (2" or 3" or 6") as specified	Sqm	9.00		
	Sub Total				
	GST ___ %				
	Net Total				
	Total amount in words: Rupees _____ _____ _____ only)				

Seal and signature of the Agency

Date:


Joint Director



NATIONAL INSTITUTE OF FASHION TECHNOLOGY,
PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210

Terms and conditions:

- 1) The NIFT reserves the right to accept or reject any quotation in part or whole without assigning any reason thereof.
- 2) Last date of receipt of sealed Quotation is 27/07/2020 upto 3.00 pm.
- 3) The quoted rates shall be valid for 60 days.
- 4) Above rate are including GST, transportation charges, labour, materials and all other charges.
- 5) Date of Completion of work: Within 30 days from the date of issue of work order.
- 6) Payment shall be made as per the actual quantity executed, no additional payment will be made.
- 7) No advance payment will be made.
- 8) Payment will be made after satisfactory completion of work and submission of original bill with measurement.
- 9) Defect liability period for the work is one year (01 year) from the date of completion of work and release of payment.
- 10) 5% security deposit deducted from the bill and same will be released after completion of DLP of one year.
- 11) The bidder may inspect the site before quoting their competitive rates.
- 12) To complete the work if required any additional work same will be carry out without any additional cost, no payment made for this purpose.
- 13) GST No: _____ Pan No: _____
- 14) Copy of GST and Pan Card to be submitted along with quotation.

Name & Address of the Company:

Mobile No.: _____

Seal and signature of the Agency

Date:


Joint Director